

6th Avenue NE (18th Dr to 19th St NE) & 18th Drive NE (from 5th Ave to 6th Ave NE)

Project Scope

Below is the general order of construction on the project:

- Removal of the existing asphalt pavement and curb & gutter
- Sanitary sewer replacement
- Austin Utilities replacement of water main and services
- Storm sewer replacement
- Roadway excavation
- Installation of drain tile and sump pump service stub outs
- Place new aggregate base in the street
- Remove and replace existing deficient sidewalk
- Construct pedestrian ramps where sidewalks meet the street
- Pour new concrete curb and gutter
- Driveway approach replacement
- Asphalt paving
- Boulevard restoration



Project Schedule and Phasing

- Bid Project in March

Phase	Start Date	Estimated Completion
6 th Avenue NE	July 2025	October 2025
18 th Drive NE	July 2025	October 2025

Project Costs

Category	Funding Source	Estimated Cost
Street Improvements	Assessments, Local Tax Levy	\$520,000
Storm Sewer Improvements	Stormwater Utility Fees	\$130,000
Sanitary Sewer Improvements	Wastewater Treatment Utility Fees	\$250,000
	Total	\$900,000

Project Updates

Once work begins, weekly project updates are posted on the City of Austin construction website and via text message.

<https://www.ci.austin.mn.us/public-works/city-construction-projects>

For any other questions please contact:

Andrew Sorenson, PE

Assistant City Engineer

ASorenson@ci.austin.mn.us

507-437-9950

Scan here to visit the
City of Austin
construction website

