

8th Street NE (15th Ave to 18th Ave NE) Institute Lift Station Construction

Project Scope

Below is the general order of construction on the project:

Phase 1

- Construction of Institute Lift Station
- Directional drilling of new forcemain under I-90 from lift station to 8th St & 10th Ave NE
- Directional drilling of gravity sanitary sewer under I-90
- Austin Utilities replacement of water main on 15th Ave NE
- Reconstruction of 15th Ave NE

Phase 2

- Removal of the existing concrete pavement on 8th St NE
- Sanitary replacement on 8th St NE and portion of 9th St NE
- Removal of Weyerhaeuser Lift Station
- Austin Utilities replacement of water main and services
- Storm sewer improvements
- Roadway excavation
- Place new aggregate base in the street
- Remove and replace deficient sidewalk
- Construct pedestrian ramps where sidewalks meet the street
- Construct new concrete pavement
- Driveway replacement
- Boulevard restoration



Project Schedule and Phasing

Phase	Start Date	Estimated Completion
Phase 1 – Institute Lift Station Construction	May 2024	July 2024
Phase 2 – 8 th Street NE	July 2024	October 2024

Project Costs

Category	Funding Source	Estimated Cost
Street Improvements	Assessments, Local Tax Levy, State Aid	\$1,150,000
Storm Sewer Improvements	Stormwater Utility Fees	\$50,000
Sanitary Sewer Improvements	Wastewater Treatment Utility Fees	\$1,200,000
	Total	\$2,400,000

Project Updates

Letters will be handed out approximately 1 week prior to work starting on each phase. Once work begins, weekly project updates are posted on the City of Austin construction website and via text message.

<https://www.ci.austin.mn.us/public-works/city-construction-projects>

For any other questions please contact:

Mitch Wenum, PE
Assistant City Engineer
MitchW@ci.austin.mn.us
507-437-9950

Scan Here to visit
the City of Austin
construction
website

